BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work:- Construction of Compound Wall for the Indira Canteen in Ward No-02.

Sl	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
1	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 141/ Item No. 19.1/ PWD SR 2016-2017	Cum	49.39	88.56	Rupees eighty eight and paise fifty six only
2	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications including cost of gravell/murrum,watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. (Page No. 147 & Item No. 19.60)	Cum	33.52	326.16	Rupees three hundred twenty six and paise sixeen only
3	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/(PWD SR 2016-2017)	Cum	80.21	305.64	Rupees three hundred five and paise sixty four only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
4	KSRB 2.11: Providing sand cement bed with 10% cement with all leads for all materials and lift of 1.5 m. machine mixed, laid in layers of 15cms. thick and well compacted for foundation, including curing cost of materials labour and HOM complete as per specifications. specification. No. KBS (P.6/I.2.18 PW, P & IWTD -SR 2016-2017)	Cum	52.00	4030.56	Rupees four thousand thirty and paise fifty six only
5	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregate @ 0.892cum and fine aggregates @ 0.465cum machine mixed, machinemixed, concrete laid in layers not exceeding 15 cms, thick well compacted in foundation and plinth, cost of all materials, labour HOM of machinery, curing complete as per specifications.(P.no.12 item no-4.2)	Cum	12.48	5449.68	Rupees five thousand four hundred foty nine and paise sixty eight only
6	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No. 23/ Item No. 5.6)	Cum	33.86	4521.96	Rupees four thousand five hundred twenty one and paise ninety six only
7	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.22/I.5.9 PW, P & IWTD -SR 2016-2017)	Cum	8.48	5405.40	Rupees five thousand four hundred five and paise forty only
8	KSRRB M100-1 Loading and un loadingofstoneboulder/Stone/aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader, dumping, turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no 133, PWD SR 2016-17)	Cum	129.60	108.00	Rupees one hundred eight only

EXECUTIVE ENGINEER-4
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.